BRUHAT BANGLORE MAHANAGARA PALIKE

DASARAHALLI-ZONE

T.DASARAHALLI-SUB-DIVISION.

Name of Work: Improvements to roads and drains at Havnoor Layout in Bagalagunte Ward No.14, T.Dasarahalli Sub Division.

Estimate Cost :-19.00 Lakhs

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work: Improvements to roads and drains at Havnoor Layout in Bagalagunte Ward No.14, T.Dasarahalli Sub Division.

			Est. Cost Rs.				19.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.141/I.19.1 PW, P & IWTD -SR 2016-17								
	6, 7, 8 & 9 cross Havnoor layout	Cum	1	387.00	5.00	0.15	290.25		
	Basic Rate	82.00					290.25	86.92	25229.00
	Add Area Weightage 6%	4.92							
	Total	86.92							
2	KSRRB M400-1 For Grading I material construction of **granular sub-base** by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material . Page No 155/ Item No. 20.6.1 PWD SR 2016-17								
		Cum	1	387.00	5.00	0.10	193.50		
	Basic Rate	1433.00					193.50	1518.98	293923.00
	Add Area Weightage 6%	85.98							
	TOTAL	1518.98							
3	Providing, laying, spreading and compacting graded stone aggregates to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158, I No.20.18)								
	Roads	Cum.	1	387.00	5.00	0.23	445.05	1768.08	786884.00
	Basic Rate	1668.00							
	Add Area Weightage 6%	100.08							
	Total	1768.08							

	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
4	Providing and applying **primer coat** with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWDSR 2016-17, P.No.161, I No.21.6)								
		Sqm	1	387.00	5.00		1935.00		
	Basic Rate	26.00					1935.00	27.56	53329.00
	Add Area Weightage 6%	1.56							
	Total	27.56							
5	Providing and laying **bituminous concrete** with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr II (30 mm to 45 mm) with 6% VG-30 Bitumen (p-164, lt 21.22 c) PWD SR 2016-17								
		Cum	1	387.00	5.50	0.05	95.78		
	Basic Rate	6859.00				0.045	95.78	7270.54	696390.00
	Add Area Weightage 6%	411.54					.		696372.00
	Total	7270.54							
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17								
		Cum	Qty Vide Item No. 1				290.25	85.65	24859.00
	Loading and	68.00						80.80	23452.00
	Lead 4 KMs	12.80							
		80.80	(2.5 x 1.28 x 4)						
	Add Area Weightage 6%	4.85							
	Total	85.65							
7	Quality control Test Charges 1%								19000.00

ನಂ. CE/D2/AS/61/16-17 ದಿನಾಂಕ : 09/1/17

ರೂ. ಸಹಸ್ರಂಭಕ್ಕು ಲಕ್ಷಗಳಲ್ಲಿ ಮಾತ್ರ/-

Rs. Nineteen lakhs only/-

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/18/16-17 ದಿನಾಂಕ : 10.01.17

Nineteen lakhs

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂ

ಕಾರ್ಯಪಾಲಕ ಅಭಿ
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ